



**Notes:**

- Inlets and outlets can be placed per contractor specifications
- Rebar design can be adjusted to customer specifications
- Manhole/Riser sizes can be adjusted to customer specifications
- 4,000 PSI Concrete
- Built to ASTM C1227 Standards

Weight of top and bottom sections: 7,710 lbs.

Weight of Middle sections: 3,472 lbs.

~48.6875 gal/inch

6" floor and lid thickness also available.

Inlet and Outlets can be placed as customer requires



**SI Precast**

Modular Commercial Jet Tank

Customer: Si Precast

Drawn By: CC

Date: 08/18/2020

File: modularcommercialjettank.dwg

Scale: NTS

Sheet: 1